

भाअजप्रा



भारतीय अन्तदेशीय जलमार्ग प्राधिकरण
INLAND WATERWAYS AUTHORITY OF INDIA

(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:

गायघाट, पोस्ट - गुलजारबाग, पटना - 800007

फोन : 0612-2310026

फैक्स : 0612-2310029

Regional Office:

Gaighat, P. O. - Gulzarbagh,

Patna - 800007

Phone/Tele fax : 0612-2310026/29

E-mail: dirpat@iwai.gov.in

File No. 4-IWAI-P-SUR (65) RIS Phase-2/2026-27/325

Date: 23.06.2026

NOTICE INVITING QUOTATION

Quotations in sealed envelope are hereby invited from experienced contractors/agencies for "Supply, installation & commissioning of borewell with submersible pump complete in all respect at Munger RIS site" as per terms & conditions given below. The details of the work and B.O.Q are enclosed as Annexure - I with this N.I.Q.

Sealed quotations will be received up to **3:00 PM on 07.07.2026 at the Regional Office of the Director, I.W.A.I, P.O - Gulzarbagh, Patna 800007 and will be opened on same day at 3:30 PM.**

The contractors/agencies or their authorized representatives (with authorization letter) who have submitted the quotations may also be present during opening of same by the committee members of R O Patna.

Rates must be quoted inclusive of all charges but excluding GST. The rates shall be quoted legibly both in figure and words and shall be valid up to 30 (Thirty) days from the date of opening. The name of the work should be clearly written on the sealed envelope.

I.W.A.I. reserves the right to accept or reject any or all quotation(s) without assigning any reason thereof.

Terms and Conditions:

- 1.0 The quotation shall be submitted in two separate sealed covers, namely Cover-I (Technical Bid) and Cover-II (Financial Bid), both of which shall be placed in one outer sealed envelope clearly superscribed with the NIQ number and subject.
- 2.0 The quotation must accompany copy PAN card, GST registration, valid Trade License, firm registration certificate, cancel cheque / Bank mandate.
- 3.0 The contractors/agencies shall be submitted experience of similar works for supply, installation & commissioning of borewell with submersible pump / tubewell at any Government/Quasi-Government/P.S.U. within last 7 years.
- 4.0 The contractors/agencies are requested to inspect the site before submitting the budgetary rate / quotation. Any clarification, you may contact IWAI, Director during the office working hour i.e. 10:00 to 17:00 hrs.
- 5.0 The agency has to quote its rate and amount only inclusive of all expenses like materials, labour, transportation to site etc including GST. As per CPWD DSR manual of sl.no:6.2 the effect of GST@18% on works contract has been incorporated in all items. No other type of quotation will be considered.

मुख्य कार्यालय :ए-13, सेक्टर-1, नोयडा,

जिला-गौतमबुद्ध नगर(उ० प्र०)

फोन : 0120-2544036/4009/4041/2521664

HEAD OFFICE: A-13, SECTOR-1, NOIDA,

Gautam Budh Nagar (U.P.) : 201301

E-mail: iwainoi@nic.in, website: www.iwai.nic.in

- 6.0 The work to be carried out as per the BOQ (Annexure-I) and as per directives of the Director, IWAI, Patna or his authorised representative.
- 7.0 The materials to be supplied as per BOQ must be of standard quality and as per specifications and free from all the defects or as per directives of the Director or his authorised representatives.
- 8.0 The work to be completed within 10 (Ten) days from the date of the work order.
- 9.0 The firm will be required to submit original Tax-Invoice after satisfactory completion of the work at the time of submission of the claim.
- 10.0 No part payment will be admissible during supply, installation & commissioning of borewell.
- 11.0 The 90% payment of the total work value will be released only after verification / satisfactory completion of the work and necessary certification by E.I.C or his Authorized representative within 15 days from the date of submission of bill. Payment will be made as per actual measurement after deduction of statutory dues.
- 12.0 The balance 10% amount with held in form of Security Deposit, the same will be released after satisfactory completion of the warranty period which is 06 (Six) month from the date of commissioning.
- 13.0 If any defect arises during the warranty period, the agency shall repair or rectify the same at its own cost and risk. No additional payment shall be made or released to the firm on this account.
- 14.0 Incomplete quotations will be summarily rejected.
- 15.0 On delay in work L.D. @ 0.5% per week will be deducted from the final payment and maximum of 10% of the work value.
- 16.0 The quotation can be downloaded from I.W.A.I. website i.e. www.iwai.nic.in



(Arvind Kumar)
Director

Encl: As above

Copy to:

1. IWAI Website
2. Notice board, IWAI, Patna Office.

Bill of Quantity (BOQ)

Annexure - I

B.O.Q for Supply, installation & commissioning of borewell with submersible pump complete in all respect at Munger RIS site					
Sl no.	Description of works	Unit	Qty	Rate (in Rs)	Amount (in Rs)
1	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge, upto 32 metre depth below ground level for All types of soil: 300 mm dia.	Meters	32		
2	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge for 200 mm nominal size dia pipe.	Meters	30		
3	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming to IS: 12818, including hire & labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge for 150 mm nominal size dia pipe.	Meters	30		
4	Gravel packing in tubewell construction in accordance with IS: 4097, including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer-in-charge.	Cum	0.25		
5	Supply and fixing of Sanitary seal cement concrete top in Complete as directives by EIC or his representative	Job	1		
6	Supplying, Installation, Testing and Commissioning of three phase open well ISI Marked submersible pump set of 1.5H.P. capacity suitable for operation on 415 V (+-10%), 3- phase AC supply compatible for operations on dynamic variable frequency / speed having IP 68 Protection including providing required no's of heavy duty M.S clamps made of flat iron and suitable size top cover made of suitable thick MS	Each	1		

	sheet as required. and making of flexible IP68 cable connections etc. complete of suitable head and discharge etc. complete as required.				
7.	Supply and installation of MS rope for lowering pump in Complete as directives by EIC or his representative.	Meter	35.00		
8.	Supply and installation of MS clamps, hardware in Complete as directives by EIC or his representative	Job	1.00		
9	Supplying & fixing PVC insulated PVC sheathed copper conductor submersible flat cable ISI Marked : 3 Core 1.5 Sq mm Flat Cable	Meter	10		
10	Supply and installation of Starter, overload & basic control panel in Complete as directives by EIC or his representative	Job	1		
11	Earthing with G.I. earth pipe 4.5 Meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. (but without charcoal/ coke and salt) as required.	Job	1		
12	Supply and services for Brick work with common burnt clay F.P.S (non modular) with a cover (1:4 mortar ratio) in Complete as directives by EIC or his representative.	Cum	0.54		
13	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply and all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as directives by EIC or his representative.	Meter	10		
	Total amount including GST				

Rupees.....

Signature of the Authorised Representative

Name of the Agency with seal.....