




भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:- 6, डुमायून एवेन्यू, कोलकाता-700043

Regional Office: 6, Dumayune Avenue, Kolkata - 700 043

Telephone no.: +913324390393 **e-mail :** dirkol@iwai.gov.in

Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

E 383169 IWAiko-150MN40/1/2026 / 638

19.08.2026

NOTICE INVITING QUOTATION

Scaled quotations are invited from the reputed Contractor/ repairer/ authorized dealer for the Annual Afloat repair of IWAI crane pontoon C.P. Ganga II as per annexure & terms and conditions laid down below. The NIQ can also be downloaded from IWAI's website (www.iwai.nic.in).

- (2) The Supply/Repair works should be done as per following terms and conditions mentioned below:
- (i) The rate may be quoted in both words and figures in annexure.
 - (ii) The price should be quoted inclusive of labour charges, loading-unloading and transportation etc. **No other charges will be entertained.** GST will be extra as applicable. Tentative cost of spares upto Rs. 1,50,000.00/- to be reimbursed on actual plus 10% basis subject to supply and fitment of spares as per OEM norms and submission of bills and challan with duly certification of officer concerned.
 - (iii) The supply/repair work must be completed within 30 days from the date of receipt of order from R.O. Kolkata.
 - (iv) The firm must submit documentary evidence, including a copy of the PAN, GST details, bank details (a copy of a cancelled cheque), and proof of similar work experience.
 - (v) The payment will be made by RTGS within 15 days from the date of receipt of bill and challan with certificate and duly certification of officer concern, after deducting the statutory dues if any. 90% payment will be release on completion of work. Remaining 10% will be release after completion of Guarantee period of six months.
 - (vi) In case of delay in supply work liquidity damage @ 1.5% per month subject to a maximum of 10% will be charged.
 - (vii) Warranty period of aforesaid supply work should be 6 months.
 - (viii) IWAI reserves the right to accept or cancel any / all quotations without assigning any reason or any prior notice.
- (3) The scaled quotation should reach this office latest by **31.08.2026** at **15:00 hrs.** No quotation will be accepted after the last date and time for submission of quotations.

Encl.: As stated above.

(Kuldeep Singh)
Director

Copy to: Notice Board, IWAI Kolkata.

Annex.

BoQ for Annual Afloat repair of IWAI crane pontoon C.P. Ganga II

	DESCRIPTION OF WORK	UNIT	QTY	Rate	AMOUNT (₹)
1.00	Chipping, Scrapping, wire brush, cleaning and Painting of all ship side area from LWL to main deck alongwith all accessories including deck fittings, crane, cabin etc. to be done by with one coat of zinc chromate yellow primer followed by two coats of existing colour anti crossive marine paints and Name of Vessel, IWAI and IWAI Logo to be painted as required as per direction of Surveyor/ EIC.	Comp. Job	1	1,39,500.00	1,39,500.00
2.00	All manhole and hatch etc's cover gasket has to be replaced. Nut bolts has to be replaced with Stainless Steel as required as per direction of EIC/ Surveyor.	Comp. Job	1	60,500.00	60,500.00
3.00	Crane Engine, Water leakage observed from radiator, same to be rectified with proper cleaning, Complete overhauling of Engine (Make: Ashok Leyland Model: ALU 6.65, 106 BHP @ 2400 rpm) is to be done with checking/calibration / renewal/ servicing of liner, piston, rings, valves, heads, fuel pump, injector, crank thrust clearance, self starter, stop solenoid, dynamo and cleaning of all coolers etc. along with renewal of spares e.g. meters, gauges, V-belts, hose pipes etc. renewal of all filters, coolants, lube oil etc., checking/rectification of all safety systems etc. as required as per direction of EIC/Surveyor.				
3.01	Labour charges	Comp. Job	1	50,000.00	50,000.00
3.02	Cost of spares (on Actual + 10 % basis)				On actual + 10% basis
4.00	Deck crane Operator cabin bottom plate found corroded, water entering from glass windows, mechanical lock to stop crane rotation found broken, Engine cabin roof found corroded/damaged. Above works are to be repaired/rectified as required as per direction of EIC/Surveyor.	Comp. Job	1	35,000.00	35,000.00
	Sub Total (in Rs.)				2,85,000.00
	Quoted price in (+/-) Percentage (%)				
	Total (excl. GST)				
	Total (In Words)				

* GST extra as applicable.

