



भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:- 6, डुमायून एवेन्यू, कोलकाता-700043

Regional Office: 6, Dumayune Avenue, Kolkata - 700 043

Telephone no.: +913324390393 **e-mail :** dirkol@iwai.gov.in

Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

File no.IWAIKo-140TC40/1/2025-Cvl(Kol)

Date:-20-08-2026

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of Parking shed, raising of floor height at checkpoint & sunshade of security room, and construction of wooden rack over the toilet passage area on the 1st floor at RO, IWAI, Kolkata" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed at RO, IWAI, Kolkata within 15 (Fifteen) days from the date of receipt of the work order as per direction of E.I.C or his representative.
3. 90% payment shall be released by RTGS/NEFT/PFMS after submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% will be released after completion of guarantee obligation period of 6 month on duly certification of the officer concerned.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 10% will be charged.
5. The firm should submit self-certified copy of PAN Card, Firm registration or working experience with IWAI, similar type work experience (work completion certificate), GST registration and cancelled cheque etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 25-08-2026 at 1500 hrs. The sealed bids will be opened on same at 1530 hrs.

(Kuldeep Singh)
DIRECTOR

BoQ for Construction of Parking shed, raising of floor height at checkpoint & sunshade of security room and construction of wooden rack over the toilet passage area of 1st at RO, IWAI, Kolkata

S. no.	Description of Items	Unit	Qty.	Rate (in Rs.)	Amount (in Rs.)
1	Raising of floor height at checkpoint & sunshade of security room				
1.01	Providing & laying in position cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) in floor all complete as per specification & direction of EIC	cum	6.97		
1.02	Supplying, fitting & fixing of MS angle 75x75x6 for frame of sun shade all complete as per specification & direction of EIC	kg	40.80		
1.03	Supplying , fitting & fixing MS flat (75 x 6) in hypotenius support all complete as per specification & direction of EIC	kg	14.85		
1.04	Supplying, fitting & fixing color coated 0.6mm thick sheet for sunshade all complete as per specification & direction of EIC	sqm	3.10		
2	Construction of wooden rack over the toilet passage area of 1st (Area = 6.85m x 1.251m)				
2.01	Supplying & Erecting of RHS (100 x 50 x 5) in vertical post all complete as per specification & direction of EIC	kg	187.48		
2.02	Supplying , fitting & fixing MS flat (100 x 6) in horizontal for bottom support all complete as per specification & direction of EIC	kg	47.04		
2.03	Suppluing, fitting & 18mm thick plyboard all complete as per specification & direction of EIC	sqm	8.57		
3	Construction of Parking shed Area to be covered = 9.3m x 4.5m				
3.01	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge	cum	1.25		

3.02	Providing & laying in position cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) in floor all complete as per specification & direction of EIC	cum	0.13		
3.03	Supplying, fitting & fixing SHS (100 x 5) n vertical posts all complete as per specification & direction of EIC	kg	381.17		
3.04	Supplying, fitting & fixing rafter (RHS 100x50x5) all complete as per specification & direction of EIC	kg	367.31		
3.05	Supplying, fitting & fixing header/beam on both side (RHS 100x50x5) all complete as per specification & direction of EIC	kg	202.74		
3.06	Supplying, fitting & fixing purline (RHS 100x50x3) all complete as per specification & direction of EIC	kg	212.625		
3.07	Supplying, fitting & fixing 0.6mm thick color coated sheet all complete as per specification & direction of EIC	sqm	50.38		
Sub Total excluding GST					