



भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:- 6, डुमायून एवेन्यू, कोलकाता-700043

Regional Office: 6, Dumayune Avenue, Kolkata - 700 043

Telephone no.: +913324390393 **e-mail :** dirkol@iwai.gov.in

Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

File no. IWAIKo-140TC12/1/2025-CvI(Kol)

Date: 20-08-2026

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Repair & Renovation of pipa pontoon, linking platform of pipa pontoon, walkway, sign board and construction of 2 nos mooring pins at Saptrishi ghat, Tribeni" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed within 10 (Ten) days from the date of receipt of the work order as per direction of E.I.C or his representative at Saptrishi ghat, Tribeni.
3. 90% payment shall be released by RTGS/NEFT/PFMS after submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% will be released after completion of guarantee obligation period of 6 month on duly certification of the officer concerned.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 10% will be charged.
5. The firm should submit self-certified copy of PAN Card, Firm registration or working experience with IWAI, similar type work experience (work completion certificate), GST registration and cancelled cheque etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 25-08-2026 at 1500 hrs. The sealed bids will be opened on same at 1530 hrs.

(Kuldeep Singh)
DIRECTOR

BoQ for Repair & Renovation of pipa pontoon, linking platform of pipa pontoon, walkway, sign board and construction of 2 nos mooring pins at Saptrishi ghat, Tribeni

S. no	Description of Items	Unit	Qty	Rate (in Rs.)	Amount (in Rs.)
1	Repair & Renovation of pipa pontoon, linking platform of pipa pontoon, walkway				
1.01	Supplying, fitting, fixing & fabrication 10mm thick chequered of deck linking pipa pontoon all complete as per specification & direction of EIC	kg	83.40		
1.02	Supplying, fitting, fixing & fabrication 40NB MS pipe of wall thickness 3.2mm for hand rail of linking platform of pipa pontoon all complete as per specification & direction of EIC	kg	24.92		
1.03	Miscellaneous repair works of various sections by providing welding etc all complete	job	1.00		
2	Mooring Pin (2 nos)				
2.01	Earthwork in excavation all complete as per specification & direction of EIC	cum	6.75		
2.02	Providing & laying cement concrete in foundation trenches in M15 (1:2:4) all complete as per specification & direction of EIC	cum	6.75		
2.03	Supply, fabrication & erection of ISA 75x75x6 in bottom(crossed) all complete as per specification and direction of EIC.	kg	57.66		
2.04	Supply, fabrication & erection of ISMB 300 2.5m length all complete as per specification and direction of EIC.	kg	221.00		
3	Painting work & Sign board				
3.01	Scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete (Pipa Pontoon, Linking Gangway, Linking platform & Walkway)	sqm	750.00		

3.02	Supplying & applying priming with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works all complete as per specification & direction of E.I.C				
	With 1st coat	sqm	750.00		
	With 2nd coat	sqm	750.00		
3.03	Supplying & applying synthetic enamel paint of approved brand and manufacture of required colour to give an even shade on steel galvanised iron/ steel works of sign board all complete as per specification & direction of E.I.C	sqm	750.00		
3.04	Supplying, fitting & fixing 4mm thick ACP with vinyl sticker all complete as per specification & direction of EIC	sqm	5.52		
Sub Total excluding GST					