




भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:- 6, डुमायून एवेन्यू, कोलकाता-700043

Regional Office: 6, Dumayune Avenue, Kolkata - 700 043

Telephone no.: +913324390393 **e-mail :** dirkol@iwai.gov.in

Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

File no. IWAIKo-140TC7/1/2026-CvI(Kol)

Date: 05-09-2026

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of a 20m x 2m Bamboo Jetty/Walkway, Two Mooring Pins, and Jungle Clearance at Metiary" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed within 10 (Ten) days from the date of receipt of the work order as per direction of E.I.C or his representative at Metiary.
3. 90% payment shall be released by RTGS/NEFT/PFMS after submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% will be released after completion of guarantee obligation period of 6 month on duly certification of the officer concerned.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 10% will be charged.
5. The firm should submit self-certified copy of PAN Card, Firm registration or working experience with IWAI, similar type work experience last 7 years(work completion certificate), GST registration and cancelled cheque etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 08-09-2026 at 1500 hrs. The sealed bids will be opened on same at 1530 hrs.

(Kuldeep Singh)
DIRECTOR

BoQ for Construction of a 20m x 2m Bamboo Jetty/Walkway, Two Mooring Pins, and Jungle Clearance at Metiary					
S.no	Description of Items	Unit	Quantity	Rate (in Rs.)	Amount (in Rs.)
1	Bamboo Jetty				
1.01	Providing & driving treated 6m long bamboo piles of 100mm dia all complete as per specification & direction of EIC	meter	252.00		
1.02	Supplying & fixing bamboo cross bracing and walers(horizontal support for bracing) all complete as per specification & direction of EIC.	meter	420.00		
1.03	Providing 100mm dia logitudinal bamboo beams all complete as per specification & direction of EIC (3 rows)	meter	60.00		
1.04	Providing bamboo joists (below deck)@0.5mc/c all complete as per specification & direction of EIC	meter	82.00		
1.05	Providing treated split bamboo decking (50mm thick) all complete as per specification & direction of EIC (20m x 2m)	meter	40.00		
1.06	Providing bamboo handrail (1m height) on both sides all complete as per specification & direction of EIC	meter	40.00		
1.07	Providing nuts, bolts, clamps, binding wire and coir rope all complete as per specification & direction of EIC	Job	1.00		
2	Surface dressing/cleaning of terminal area including removing of vegetations not exceeding 15cm deep and disposal of upto 50 meter all complete as per specification & direction of EIC	sqm	500.00		
3	Mooring Pins (2 nos)				
3.01	Earthwork in excavation all complete as per specification & direction of EIC	cum	6.75		

3.02	Providing & laying cement concrete in foundation trenches in M15 (1:2:4) all complete as per specification & direction of EIC	cum	6.75		
3.03	Supply, fabrication & erection of ISA 75x75x6 in bottom(crossed) all complete as per specification and direction of EIC.	kg	57.66		
3.04	Supply, fabrication & erection of ISMB 300 2.5m length all complete as per specification and direction of EIC.	kg	221.00		
Sub Total Excluding GST					