



भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)



क्षेत्रीय कार्यालय:- 6, डुमायून एवेन्यू, कोलकाता-700043

Regional Office: 6, Dumayune Avenue, Kolkata - 700 043

Telephone no.: +913324390393 **e-mail :** dirkol@iwai.gov.in

Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

IWAIKo-150MN43/1/2025-DIR (Kol) / 865

14.10.2026

NOTICE INVITING QUOTATION

Scaled quotations are invited from the reputed Contractor/repairer/dockyard for the ***afloat repair of SL Dwarkeswar at NW-1*** as per annexure & terms and conditions laid down below. The NIQ can also be downloaded from IWAI's website (www.iwai.gov.in).

(2) Pricing and Quoting Guidelines: -

- The price for labour charge shall be quoted in both figures & words in the annexure.
- The price should be quoted inclusive of labour charges, loading-unloading etc. No additional charges will be entertained. GST will be extra as applicable. The cost of spares will be paid on actual + 10% basis, subject to the spares being fitted and supplied within the estimated cost amount up to ₹65,000/- Excl. GST (on actual plus 10%).

(3) Required Documents: -

- The firm must submit documentary evidence, including a copy of the PAN, GST details, bank details (a copy of a cancelled cheque).
- The firm shall submit documentary evidence of adequate experience and technical expertise in FRP (Fibre Reinforced Plastic) repair of inland vessels, including afloat repair of vessels and technical know-how for satisfactory execution of the work.
- Bidders must accept all the terms and conditions of this NIQ and must submit a duly signed and stamped copy of this NIQ document along with the quotation.

(4) Work Execution & Timeline: -

- The repair work must be completed within 20 days from the date of handed over of the vessel to the repairer.
- In Case of delay in completion of work, liquidity damage @ 1.5% per month to be computed on per day basis subject to a maximum of 10 % will be charged.

(5) Payment Terms & Warranty: -


- Payment will be made via RTGS within 15 days from the date of successful work completion and bill certification by the concerned officer, after deduction of statutory dues. Ninety percent (90%) of the payment will be released upon completion of the work and remaining 10% amount will be converted into Security Deposit. The payment of the cost of spares will be made on actual + 10% after submission of the GST bill of the spares.

- ii. The aforesaid repair work shall carry a **6-month** warranty at anywhere under the jurisdiction of RO Kolkata. The 10% security deposit will be refunded upon successful completion of the warranty period.

(6) Rights of the Authority: - IWAI reserves the right to accept or cancel any / all quotations without assigning any reason or any prior notice.

(7) Submission Deadline: - The sealed quotation should reach this office latest by 22.10.2026 at 1300 hrs. No quotation will be accepted after the last date and time for submission of quotations.

Encl: as stated above.


(Kuldeep Singh)
DIRECTOR

Copy to: - Notice Board, IWAI Kolkata.

Annex

Quotation for Afloat repair of SL Dwarkeswar for the year 2026-27					
SL. NO	DESCRIPTION OF WORK	UNIT	QTY	Rate (₹)	Amount (₹)
1.0	The entire ship side from LWL to main deck, deck plate, bathroom, galley, engine room, store tooms, fresh water tanks, fore peak tank/void tanks, etc. are to be properly cleaned, scrapped, wire brushed, chipped and painted by 3 coats of existing colour marine paint. (1 coat zinc chromate primer, followed by two coats of existing colour of marine paints). All pipe lines should be coloured as per marine colour code. After it name of vessel, department logo, all door's/hatches opening and closing indication mark to be made by paint as required as per direction of EIC/Surveyor.	Comp. Job	1		
2.0	2 Nos. of twin bollard (Aft Lower deck near steering compartment) found thinned down, rusted and holed, Steering gear compartment hatch cover and hatch coaming found rusted and thinned down, etc to be repaired/rectified and also Cropping & renewal of deck & superstructure plates including main deck, Roof area, guard rail, deck plate, Ship side plate up to LWL, other fitments as required as per direction of EIC/Surveyor.	Comp. Job	1		
3.0	All manhole covers, all window, outside doors, air vents & all hatches/ Tank cover with damaged rubber packing/ beading, nuts, bolts & studs same to be repaired/ renewed by good quality of rubber packing/ beading & SS fittings respectively as per direction of EIC/Surveyor.				
3.1	Labour charges	1	Comp. Job		
3.2	Cost of spares (actual + 10%)		L.S.		on actual + 10% basis



4.0	Engine room blower Aft (P) found non-operational, Sewage pump found with leakage and abnormal noise., Engine room light found inadequate, sufficient lights to be installed as applicable and also all the above defects to be rectified/repared and also all the electrical and electronics lines and equipment to be checked and repaired/rectified as required as per direction of EIC/Surveyor.				
4.1	Labour charges	Comp. Job	1		
4.2	Cost of spares (on Actual + 10 % basis)				on actual + 10% basis
5.0	Supply of Lifebuoy 2.5, Type: safe buoy 25, IRS approved with EC type certificate	Nos.	4		
6.0	Joint between Wheelhouse structure FRP and upper main deck steel structure both (P & S) side found holed and temporary repairs noted and also officer cabin 1 no. window glass (Aft) found missing etc. same are to be repaired/rectified/renewed as required as per direction of EIC/ Surveyor.	Comp. Job	1		
Total labour cost (Excl. GST) (₹)					
Rupees _____					

* GST extra as applicable.

* Cost of spares will be as per on actual + 10% basis.

