भारतीय अंतर्देशीय जलमार्ग प्राधिकरण
(पत्तन, पोत परिवहन और जलमार्ग मंत्रालय, भारत सरकार)
INLAND WATERWAYS AUTHORITY OF INDIA
(Ministry of Ports, Shipping and Waterways, Govt. of India)
क्षेत्रीय कार्यालयः- 6, डुमायून एवेन्यू, कोलकाता-700043
Regional Office: 6, Dumayune Avenue, Kolkata - 700 043
Telephone no.: +913324390393 e-mail : dirkol@iwai.gov.in
Follow us: iwai.nic.in @IWAI_ShipMin iwai_shipmin_india IWAI_ShipMin @IWAI_ShipMin

IWAIKo-140TC16/1/2025-Cvl(Kol) Date:-23-11-2026

NOTICE FOR INVITING QUOTATION

Sealed quotations are invited from reputed and experienced contractors for the work of "Construction of a Channel-piling and sheet retaining structure for the yoke stage and its allied structures at the Kolaghat terminal" as per the annexure enclosed herewith on the following terms and conditions.

TERMS & CONDITIONS

1. The price may be quoted including all the costs such as labour, taxes, materials, transportation etc except GST.
2. The work shall be completed at, Kolaghat terminal within 10(Ten) days from the date of receipt of the work order as per direction of E.I.C or his representative.
3. 90% payment shall be released by RTGS/NEFT/PFMSafter submission of bill and duly certification of the bill by the officer concerned after deduction of the statutory dues if any. Balance 10% will be released after completion of guarantee obligation period of 6 month on duly certification of the officer concerned.
4. In case of delay in completion of works, liquidated damage @1.5% per two days subject to a maximum of 10% will be charged.
5. The firm should submit self-certified copy of PAN Card, Firm registration or working experience with IWAI, similar type work experience (work completion certificate alongwith work order), GST registration and cancelled cheque etc.

The sealed quotations should be reach to IWAI, Kolkata office latest by on or before 28-11-2026 at 1500 hrs. The sealed bids will be opened on same at 1530 hrs.

(Kuldeep Singh)
DIRECTOR

Copy for information:
1) IWAI, Notice board

BoQ for Construction of a Channel-piling and drum-sheet retaining structure for the yoke stage and its allied structures at the Kolaghat terminal.					
S. no.	**Description of Items**	**Units**	**Qty.**	**Rate (in Rs.)**	**Amount (in Rs.)**
1	Supplying ISMC 300 10 m long(Piles) all complete as per specification & direction of EIC	kg	2,178.00	113.3720339	2,46,924.29
2	Labour for driving ISMC 300 8m below GL all complete as per specification & direction of EIC	r-m	48.00	500	24,000.00
3	Supplying of MS flat 100 x 6 in horizontal runners all complete as per specification & direction of EIC	kg	150.72	113.3720339	17,087.43
4	Supplying, fitting and fixing color coated sheet in all three sides all complete as per specification & direction of EIC	sqm	38.40	1200	46,080.00
5	Supplying and fitting of M 24 mm x 100 mm nut & bolt all complete as per specification & direction of EIC	kg	5.44	113.3720339	616.29
6	Supplying and laying of empty cement bag filled with locally available brick bats/jhama & silver sand	nos	500.00	130	65,000.00
				Total amount excluding GST	**3,99,708**
				Percentage (-/+)%	
				Grand Total amountexcluding GST	